

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20971-00-00
Spot: SESWNW Sec/Twnshp/Rge: 28-17S-27W
2983 feet from S Section Line, 4296 feet from E Section Line
Lease Name: MCBEE Well #: 1
County: LANE Total Vertical Depth: 4654 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4125		WITH 2 SX CMT
L1	4.5	4654		WITH 250 SX CMT
PROD	4.5	3727	0	WITH 250 SX CMT
SURF	8.625	413		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2017 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: AVEN WEAVERLING Company: DAMRA RESOURCES Phone: (785) 625-0020

Proposed
Plugging
Method:

CIBP @ 4200' WITH 2 SX CMT. PERFORATE AT 2100' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2017 9:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

FOUND WELL RECORDS AFTER THE WELL WAS PERFORATED STATING THEY HAD RUN A LOG FOUND CMT FROM 1678' TO 738'. THEY THEN PUMPED 75 SX CMT DOWN BACKSIDE, THEN PERFORATED AT 1900' & PUMPED 225 SX CMT.SET CIBP @ 4125' WITH 2 SX CMT. PERFORATED AT 2100'. PUMPED 155 SX CMT & 150# HULLS. DID NOT CIRCULATE. PULLED TBG TO 1400' & PUMPED 90 SX CMT. DID NOT CIRCULATE. PULLED TBG & TIED ONTO BACKSIDE. COULDN'T PUMP INTO. SDON. 5/16/17: TIED ONTO CASING & PUMPED 125 SX CMT. PRESSURED TO 500#. SHUT IN.

Top	Bot	Thru	Comments
4453	4581		
4239	4306		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING. *51A*

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)

RECEIVED
MAY 18 2017
KCC DODGE CITY

INDEXED
MAY 18 2017

Form CP-2/3