

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-20985-00-01Spot: NWNWSec/Twship/Rge: 22-33S-23W4700 feet from S Section Line, 4709 feet from E Section LineLease Name: HAYDOCK (OWWO)Well #: 1-22County: CLARKTotal Vertical Depth: 5100 feetOperator License No.: 34104Op Name: DAMM RESOURCES LLCAddress: 5548 OIL CENTER RD
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5100	1500	WITH 100 SX CMT
SURF	8.625	360		WITH 200 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/27/2017 8:30 AMPlug Co. License No.: 31529Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.Proposal Revd. from: MIKE KELSOCompany: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4620' WITH 2 SX CMT. PLUG AT 950' WITH 12 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIERWitness Type: PARTIALDate/Time Plugging Completed: 04/27/2017 6:00 PMKCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

4/26/17: COULD NOT GET CIBP PAST 1720' WITH WIRELINE. SHUT DOWN. 4/27/17: RAN TBG & PUMPED BOTTOM WITH 50 SX CMT. PULLED TBG. CUT CASING AT 1500'. 1ST PLUG AT 950' WITH 15 SX GEL & 50 SX CMT WITH 100# HULLS IN THE LAST 25 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. TOPPED OFF WITH 5 SX CMT.

Top	Bot	Thru	Comments
4672	4675		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.Plugged through: CSGDistrict: 01

Signed

Larry Harris

(TECHNICIAN)

RECEIVED

MAY - 9 2017

KCC DODGE CITY

11.000000
11.000000
11.000000

Form CP-2/3