

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21004-00-02
Spot: SENWNWSE Sec/Twshp/Rge: 8-23S-22W
1982 feet from S Section Line, 2103 feet from E Section Line
Lease Name: SEBES Well #: 1-8
County: HODGEMAN Total Vertical Depth: 4620 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1500		
PROD	5.5	4619	0	WITH 100 SX CMT
SURF	8.625	268		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2017 11:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: DANIEL L KING Company: DK OPERATING Phone: (620) 357-5732

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT WITH 100# HULLS SET CIBP @ 1500'. LOAD & TEST CASING TO 500 PSI. IF HOLDS PERFORATE AT 1470' WITH 50 SX CMT WITH 200# HULLS IN LAST 25 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 05/08/2017 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO BOTTOM & PUMPED 25 SX CMT WITH 100# HULLS. PULLED TBG. SET CIBP @ 1500'. PRESSURED THE CASING TO 1000# & HELD. PERFORATED AT 1470' & 600'. RAN TBG TO 1470' & PUMPED 50 SX CMT WITH 200# HULLS IN THE LAST 25 SX CMT. PULLED TBG & TIED ONTO THE 5 1/2" CASING. DID NOT GET ANY RETURNS WHILE PUMPING THROUGH 600' PERFORATIONS. PUMPED 135 SX CMT (80 SX OVER CASING VOLUME). TIED ONTO BACKSIDE & PRESSURED TO 500# WITH 5 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4518	4522	CSG	
4512	4516	CSG	

INVOICED
JUN 14 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed  (TECHNICIAN)

RECEIVED
MAY 10 2017
KCC DODGE CITY 