

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-20978-00-00  
Spot: SENE Sec/Twnshp/Rge: 21-34S-2E  
1980 feet from N Section Line, 660 feet from E Section Line  
Lease Name: HILLS/ROSENTHAL Well #: 1-21  
County: SUMNER Total Vertical Depth: 3535 feet

Operator License No.: 3861  
Op Name: ENMARK GAS GATHERING L. P.  
Address: 17430 CAMPBELL RD STE 230  
DALLAS, TX 75252

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2908		
CIBP		3340		
PROD	4.5	3514		200 SX
SURF	8.625	221		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2017 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: BRIAN SWIGERT Company: ENMARK GAS GATHERING L.P. Phone: (214) 368-5050

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/14/2017 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

UNABLE TO GET TUBING PAST 1050', SET CIBP @ 1030', DUMPED 2 SX OF COMMON CEMENT ON TOP OF PLUG. PERFORATED CASING @ 300' AND CIRCULATED 60/40 POS-MIX TO SURFACE UNTIL ESTABLISHED GOOD RETURNS WITH 105 SX. CEMENT DID DROP AND TOPPED OFF CASING WITH 20 MORE SX. CONSOLIDATED TICKET #52084.

Perfs:

Top	Bot	Thru	Comments
3515	3517	TBG	
3380	3386	TBG	
3276	3282	TBG	
3243	3249	TBG	
2834	2845	TBG	

INVOICED  
JUN 14 2017

Remarks: WELL PLUGGED DUE TO RESPONSE TO NOV LETTER.

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

✓