

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21618-01-00
Spot: S2S2SESE Sec/Twnshp/Rge: 28-31S-20W
214 feet from S Section Line, 660 feet from E Section Line
Lease Name: EDMONSTON Well #: 1-28H
County: COMANCHE Total Vertical Depth: 5065 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5276		WITH 50 SX CMT
CIBP		7306		
CIBP		7334		
COND	20	83		
	L1 4.5	9683		WITH 475 SX CMT
PROD	7	5528	0	WITH 275 SX CMT
SURF	9.625	700		WITH 455 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2017 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 5276' WITH 50 SX CMT. PERFORATE AT 730' & CIRCULATE CMT TO SURFACE IN AND OUT 7" AND 7" X 9 5/8" ANNULUS.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2017 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

5/5/17: SET CIBP @ 5276' WITH 50 SX CMT. PERFORATE AT 730'. 5/8/17: CIRCULATED CMT FROM 730' SURFACE INSIDE 7" AND UP 7" X 9 5/8" ANNULUS WITH 280 SX CMT.

Perfs:

Top	Bot	Thru	Comments
7386	9625		
5542	9623		

INVOICED
JUN 14 2017

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENT. TMD= 9685'

Plugged through: CSG

District: 01
RECEIVED
MAY 10 2017
KCC DODGE CITY

Signed Larry Harris ECRS
JAH (TECHNICIAN)