

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20075-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 2-31S-39W
1400 feet from N Section Line, 1400 feet from E Section Line
Lease Name: SIMMONS Well #: 2-2
County: STEVENS Total Vertical Depth: 2890 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2889	0	WITH 300 SX CMT
SURF	8.625	553		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/25/2017 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2017 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

4/25/17: TBG SANDED AND STUCK AT 950'. SHOOT TBG OFF AT 915' & SPOT 20 SX CMT. TAG CMT AT 830'. PERFORATE AT 600'. 4/26/17: PUMP 335 SX CMT THROUGH PERFS WITH NO RETURNS. 4/27/17: TEST CASING TO 700 PSI HOLDING. TAG CMT IN 5 1/2" CASING AT 375'. PERFORATE AT 332' & PUMP 155 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2702	2864		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

INVOICED
JUN 14 2017

District: 01

Signed Kenny Sullivan
(TECHNICIAN)

RECEIVED
MAY 10 2017
KCC DODGE CITY