

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30178-00-01
Spot: NENENE Sec/Twnshp/Rge: 8-33S-16E
4929 feet from S Section Line, 412 feet from E Section Line
Lease Name: H HENDERSON Well #: 1A-8
County: MONTGOMERY Total Vertical Depth: 1236 feet

Operator License No.: 34779
Op Name: LR ENERGY, INC.
Address: 8150 N. CENTRAL EXPY, STE 1605
DALLAS, TX 75206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 1236 | | 150 SX |
| SURF | 8.65 | 21 | | 8 SX |
| T1 | 2.875 | 1108 | | |

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/10/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JUSTIN BARKMAN Company: _____ Phone: (620) 627-2499

Proposed
Plugging
Method:

Cement to Surface

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 03/10/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Pulled rods and tubing, ran 1" to 1100', gel hole, spotted 8 sacks cement at 1120', pulled up to 950', spotted 8 sacks cement, pulled up to 800' spotted 8 sacks cement, pulled up to 700' spotted 8 sacks cement, pulled up to 600' spotted 8 sacks cement, pulled up to 200' cemented to surface with 40 sacks cement. Cut off casing 3' below surface.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1143 | 1146 | | |
| 1086 | 1087 | | |
| 962 | 963 | | |
| 944 | 950 | | |
| 930 | 931 | | |
| 831 | 832 | | |
| 797 | 798 | | |
| 789 | 791 | | |
| 762 | 764 | | |
| 737 | 741 | | |
| 707 | 710 | | |
| 604 | 606 | | |

RECEIVED
KCC DIST #3
MAY 24 2017
CHANUTE, KS

INVOICED

JUN 14 2017

RH

Remarks:

Plugged through: TBG

District: 03

Signed

Russell Hine

(TECHNICIAN)

KCC WICHITA

MAY 30 2017

RECEIVED