

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30167-00-01
Spot: SESWSWNE Sec/Twnshp/Rge: 8-33S-16E
2317 feet from N Section Line, 2190 feet from E Section Line
Lease Name: H HENDERSON Well #: 7-8
County: MONTGOMERY Total Vertical Depth: 1254 feet

Operator License No.: 34779
Op Name: LR ENERGY, INC.
Address: 8150 N. CENTRAL EXPY, STE 1605
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1251		150 SX
SURF	8.65	21		8 SX
T1	2.875	1166		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/09/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JUSTIN BARKMAN Company: _____ Phone: (620) 627-2499

Proposed Plugging Method: Cement to Surface

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 03/09/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Pulled tubing and rods, ran 1" to 1100' gel hole, spotted 8 sacks cement, pulled up to 900' spotted 8 sacks cement, pulled up to 800' spotted 8 sacks cement, pulled up to 700' spotted 8 sacks cement, pulled up to 680' spotted 8 sacks cement, pulled up to 200', cemented to surface with 40 sacks of cement, cut off casing 3' below surface.

Perfs:

Top	Bot	Thru	Comments
1148	1151		
1094	1095		
919	922		
894	897		
822	824		
782	784		
756	758		
731	736		
702	707		

RECEIVED
KCC DIST #3
MAY 24 2017
CHANUTE, KS
INVOICED *RH*

Remarks:

Plugged through: TBG

JUN 14 2017

District: 03

Signed *Russell Hine*
(TECHNICIAN)

KCC WICHITA
MAY 30 2017
RECEIVED