

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20064-00-01
Spot: N2NENE Sec/Twnshp/Rge: 17-20S-8W
330 feet from N Section Line, 660 feet from E Section Line
Lease Name: TOBIAS Well #: 1
County: RICE Total Vertical Depth: 1337 feet

Operator License No.: 35460
Op Name: LYONS SALT COMPANY
Address: 1660 AVE. N
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	245		0 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/17/2017 10:00 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: GARY Company: STERLING DRILLING CO Phone: (620) 672-9508

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: NONE
Date/Time Plugging Completed: 05/21/2017 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

5-17-2017 @ 10:00 AM. RAN DRILL PIPE @1337'. BASIC CIRCULATED 25 SXS CLASS A COMMON AND TAGGED @ 1270'. 5-17-2017, 11:30 PM RAN DRILL PIPE @ 1270' BASIC CIRCUALTED 400 SXS SALT SAT. CLASS A COMMON AND TAGGED @ 943'. 5-19-2017 @ 12:30 AM, RAN DRILL PIPE @ 943' BASIC CIRCULATED WITH 200 SXS SALT SAT. CLASS A COMMON CEMENT AND TAGGED @ 876. 5-20-2017 @ 6:30 AM, RAN DRILL PIPE @ 876' BASIC CIRCULATED 150 SXS SALT SAT. CLASS A COMMON & TAGGED @ 823'. 5-20-2017 @ 11:00 AM RAN DRILL PIPE @ 823' BASIC CIRCUALTED 400 SXS CLASS A COMMON CEMENT AND TAGGED @ 39'. 5-21 2017 @ 3:00 PM, RAN DRILL PIPE @ 39' BASIC CIRCULATED 50 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. TOTAL 1, 225 SXS CLASS A CEMENT. 30 SXS CLASS A COMMON IN RAT HOLE AND 30 SXS CLASS A COMMON IN MOUSE HOLE. BASIC #14964.

Remarks: LYON SALT CO./ RE CEMENTED WELL FROM 1337'-0'

Plugged through: DP

INVOICED
JUN 14 2017

District: 02

Signed [Signature]
(TECHNICIAN)