

To: 1090192
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200-COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-29 API NUMBER 15-165-21,602-0000 24R

C NW SE, SEC. 24, T. 17 S, R. 19 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5027

Lease Name Foos Well # 1

Operator: J.A. Allison
Name & Address: 300 W. Douglas, Suite 305
Wichita, KS 67202-2975

County Rush
Well Total Depth 3848 125.06 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 214

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling Company License Number 5122

Address P.O. Box 308, Great Bend, KS 67530-0308

Company to plug at: Hour: 7 p.m. Day: 29 Month: 4 Year: 19 92

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling Company (phone) 316-792-2921

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 131F-37'
1st plug at 1340' with 50 sx cement, 2nd plug at 610' with 80 sx cement,
3rd plug at 240' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10 p.m. Day: 29 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1340' with 50 sx cement,
2nd plug at 610' with 80 sx cement,
3rd plug at 240' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1992
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(operator did not) observe this plugging.

DATE 5-14-92

Signed [Signature] (TECHNICIAN)

INV. NO. 352.29

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 3-23-92

State of Kansas

FORM MUST BE TYPED

D (STRICT #)

NOTICE OF INTENTION TO DRILL 165-21,602-000

FORM MUST BE SIGNED

SGA7... Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date April 25 1992
month day year

Spot C NW SE Sec 24 Twp 17 S, Rg 19 West

OPERATOR: License # 5027
Name: J. A. Allison
Address: 300 West Douglas, Suite 305
City/State/Zip: Wichita, Kansas 67202-2975
Contact Person: J. A. Allison
Phone: 316-263-2241

1980 feet from South ~~XXXXX~~ line of Section
1980 feet from East ~~XXXXX~~ line of Section

IS SECTION REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5122
Name: Woodman-Iannitti Drilling Co.

County: RUSH
Lease Name: FOOS Well #: 1

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield ... Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Field Name: _____
Is this a Prorated/Spaced Field? ... yes no

Target Formation(s): Arbuckle

Nearest lease or unit boundary: 660
Ground Surface Elevation: (Est.) 2150 feet MSL

Water well within one-quarter mile: ... yes ... no
Public water supply well within one mile: ... yes ... no

Depth to bottom of fresh water: 430'
Depth to bottom of usable water: 600'

Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 200'

Length of Conductor pipe required: 0
Projected Total Depth: 3750'

Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:

... well ... farm pond other
DWR Permit #: _____

Will Cores Be Taken?: ... yes no
If yes, proposed zone: _____

If OWWO: old well information as follows:

Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no

If yes, true vertical depth: _____

Bottom Hole Location: _____

AFFIDAVIT

200' Alt. II Req.

Exp. 9/18/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

Pusher Rich Wheeler 602
SPUD DATE 4-23-92 INIT. 92
LENGTH SURFACE PLANNED 200 FT

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbs. when done bbbs.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 214 CONDUCTOR
ANHYDRITE T- 17 1/2 B- 1337 ELEVATION

TD 3848 FORMATION Arbuckle top @ 3847

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ 40 Ft. W/ SX

Hug./Council @ 0 Ft. W/ SX
Anhydrite Base @ 1340 Ft. W/ 50 SX

1/2 Base Anyh. @ 610 Ft. W/ 80 SX
1/2, 1/2 Plug @ 0 Ft. W/ SX

Bottom Surface @ 240 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX

RAT-HOLE CIRC/W 15 SX MOUSE HOLE W/1 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SM DATE 4-28-92 Hauling

TYPE OF CEMENT 60/40 67s
STARTING TIME 7:00 (AM/PM) DATE 4-29-92

COMPLETION TIME 10:00 (AM/PM) DATE 4-29-92
CEMENT COMPANY Arbuckle