

To: 1120771 1-27
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,927-0000 115 R
SE SE NW, SEC. 19, T 21 S, R 15 W/E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9339
Operator: K & K Oil
Name & Address: P.O. Box 176
Chase, KS 67524

Lease Name Max Bird Well # 1
County Pawnee
Well Total Depth 4276 138.97 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 948

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 27 Month: 1 Year: 19 93

Plugging proposal received from Manny
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3954' w/250 sx cement, Perfs at 3727-33, 3750-60', PBTB 3800'
1st plug sand back to 3670' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 9:30 a.m. Day: 27 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3670' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 150 sx cement.
Pumping pressure 0-1000 psi and shut in 600 psi.

Rec'd 2-1-93
Rec'd 2-1-93

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED
DATE FEB 22 1993
INV. NO. 37403

Signed Oscar Rankin
(TECHNICIAN)