

1060793

318 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,237-0000

NE SE NE, SEC. 21, T 21 S, R 15

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8009

Lease Name Degner Well # 1-21

Operator: Discovery, Inc.

County Pawnee 126.75

Name & Address P. O. Box 576

Well Total Depth 3900 Arbuckle feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 654

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman-Tannitti Drilling Company License Number 5122

Address 704 Union Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 30 Month: January Year: 19 86

Plugging proposal received from Rich Wheeler

(company name) Woodman-Tannitti (phone) 316-265-7650

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1950 Anhydrite 910-934'

1st plug in the Arbuckle with 40 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 am Day: 30 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 3824' with 40 sx cement, 2nd plug at 934' with 50 sx

cement, 3rd plug at 684' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugged water well

with 5 sx cement.

RECEIVED STATE CORPORATION COMMISSION

FEB 4 1986

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE FEB 6 1986

INV. NO. 12401

1-30

CARD MUST BE TYPED

State of Kansas

15.145-21237-0000

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 21 86 month day year

API Number 15- 145-21,237 yes

OPERATOR: License # 8009 Name Discovery, Inc. Address P.O. Box 576 City/State/Zip Great Bend, Kansas 67530 Contact Person Dave Williams Phone (316) 792-5020

NE SE NE Sec 21 Twp 21 S. Rg. 15 East West 3630 Ft. from South Line of Section 330 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5122 Name Woodman-Iannitti Drlg. Co. City/State Wichita, Kansas Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet County Pawnee Lease Name Degner Well # 1-21 Ground surface elevation not available yet feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 200 Depth to bottom of usable water 300 Surface pipe planned to be set 650 Projected Total Depth 4000 feet Formation Arbuckle

If OWWO: old well info as follows. Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 1-17-86 Signature of Operator or Agent David P. Williams, President

For KCC Use: Conductor Pipe Required 350 feet Minimum Surface Pipe Required 650 feet per AG 6 This Authorization Expires 7-17-86 Approved By Move in 1-24-86

PUSHER Rick Wheeler TD 3900 FORMATION Arb. SURFACE PIPE 3824 @ 57' @ 654 ANHYDRITE 910 ELEVATION 1950 G.L. STARTING TIME & DATE 9:30 Am 1-30-86 COMPLETION TIME & DATE 9:34 FT. W/ 40 SX 1st PLUG @ 3824 FT. W/ 40 SX 2nd PLUG @ 9:34 FT. W/ 50 SX 3rd PLUG @ 684 FT. W/ 50 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ 5 SX

TECHNICIAN B.G. Titare if 50' in arbuckle w/ 40 shot and base any w/ 50 shot 2nd @ 30' out w/ 30 shot 4th @ 40'-0 50' w/ 10 10. mouse 60/40 w/ 60' well

RECEIVED STATE CORPORATION COMMISSION FEB 4 1986 CONSERVATION DIVISION

5-shots cement water well