

1 050782

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,245-0000  
C NE NE, SEC. 14, T 21 S, R 22 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4808

4620 feet from S section line

660 feet from E section line

Operator: Smokey Oil Company

Lease Name Cox Well # 41-14

Name & Address: P. O. Box 2360

County: Hodgeman 146.58

Well Total Depth 4510 Mississippi feet

Casper, WY 82602

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor True Drilling Company License Number 4708

Address P. O. Drawer 2360, Casper, WY 82602

Company to plug at: Hour: 1:00 pm Day: 19 Month: March Year: 19 86

Plugging proposal received from Buzz Montgomery

(company name) True Drilling (phone) 307-237-9301

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1400' Elevation 2210'

1st plug at 1425' with 50 sx cement,

2nd plug at 510' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 pm Day: 19 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1425' with 50 sx cement, 2nd plug at 805' with 50 sx

cement, 3rd plug at 510' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

3-31-86

STATE CORPORATION COMMISSION

MAR 31 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICE observe this plugging.

Signed Richard W. Lacy  
(TECHNICIAN)

DATE APR 1 1986

INV. NO. 13217 MAY 08 1986

3-19

FORM CP-2/3  
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date Feb. 28 1986 month day year

API Number 15-083-21,245 yld
C NE NE Sec. 14 Twp. 21 S. Rg. 22
4620 Ft. from South Line of Section
660 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

OPERATOR: License # 4808
Name Smokey Oil Company
Address P. O. Box 2360
City/State/Zip Casper, WY 82602
Contact Person G. F. Pickard
Phone (307)-266-0230

Nearest lease or unit boundary line 660 feet
County Hodgeman
Lease Name Cox Well # 41-14
Ground surface elevation 2210 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 X 2
Depth to bottom of fresh water 200
Depth to bottom of usable water 400 440
Surface pipe planned to be set 400 440
Projected Total Depth 4475 feet
Formation Mississippian

CONTRACTOR: License # 4708
Name True Drilling Company
City/State Casper, WY 82602
Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
cementing will be done immediately upon setting production casing.
Date Feb. 12, 1986 Signature of Operator or Agent C. F. Pickard Title Engineer

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 2140 feet per Alt.
This Authorization Expires 8-18-86 Approved By 2-18-86

move in 3-12-86 set 8 5/8" - 470' - 500 471

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 50 sx Base Anhydrite surf feet depth with ... sxs of ...
2nd plug @ 50 sx 30' below base surf feet depth with ... sxs of ...
3rd plug @ 10 sx 40' below surf feet depth with ... sxs of ...
4th plug @ 15 sx in rat hole feet depth with ... sxs of ...
5th plug @ feet depth with ... sxs of ...
(2) Rathole with ... sxs (b) Mousehole with ... sxs

PUSHER Bag Milligan
TD 4510' FORMATION MISS.
SURFACE PIPE 8 5/8" @ 472
ANHYDRITE 1400' ELEVATION 2210'
STARTING TIME & DATE 1:00 pm
COMPLETION TIME & DATE 4:30 pm
1st PLUG @ 1425 FT. W/50 SX
2nd PLUG @ 510 FT. W/50 SX
3rd PLUG @ 40-0 FT. W/10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 10 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ Hand - SX
CEMENT COMPANY Halliburton
TECHNICIAN D. G. Lacey
60/40 pc. (76%) sawy 2:10
Actual w/ 805
Actual w/ 805
1425 w/50 SX
805 w/50 SX
510 w/40 SX
40 w/50

MAR 31 1985

CONSERVATION DIVISION
Wichita, Kansas