

1080228

15.145.20868-0000

145-20,868

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Not Available
C NE NE, SEC. 1, T. 21 S, R. 16 W/X

TECHNICIAN'S PLUGGING REPORT

4620 feet from N SE Corner of XXX section line
660 feet from W SE Corner of XXX section line

Operator License # 6393

Lease Name Phinney Well # 1

Operator: Brougher Oil, Inc.

County Pawnee

Name & Address 614 Patton Road, Drawer 1367

Well Total Depth 3801 123.53 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 984

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 3 Month: October Year: 19 84

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3797' Open Hole

1st plug sand back to 3751' and dump 5 sx cement on top of sand through bailer

2nd plug at 1000' with 50 sx cement

3rd plug at 480' with 30 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

10-9-84
OCT 09 1984

Plugging Proposal Received by J. H. Metz
Conservation Division
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:00 pm Day: 3 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug sanded back to 3751' and dumped 5 sx cement on top of

sand through bailer, 2nd plug at 1000' with 50 sx cement, 3rd plug at 480' with 30 sx cement,

4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: They recovered 1700' of 5 1/2" casing. Cemented by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-15-84

INV. NO. 4302
10-3

Signed J. H. Metz
(TECHNICIAN)