

1 010030

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,092-0000

SW SW SE, SEC. 1, T 21 S, R 16 W/2 EX

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Foster "A" Well # 2

Operator: Brougner Oil, Inc.

County Pawnee 123.05

Name:

Address Drawer 1367

Well Total Depth 3786 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 955

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 28 Month: August Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-928-2457

were: 5 1/2" at 3773' Perfs at 3772-78'

1st plug sand back to 3720' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:38 am Day: 28 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3720' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 750 psi and shut in 700 psi

SEP 6 1985  
9-6-85  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2041' 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED  
(I did / observed) observe this plugging.

DATE SEP 10 1985

Signed Jack A. Luthi  
(TECHNICIAN)

INV. NO. 9947