

1 080473

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,082-0000

NW SW SE , SEC. 1 , T 21 S, R 16 W/EX

990 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Foster "A" Well # 1

Operator: Brougner Oil, Inc.

County Pawnee 123.05

Name & Address Drawer 1367

Well Total Depth 3786 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 973

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:45 am Day: 15 Month: January Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend (phone) 316-793-9711

were: 5 1/2" at 3773' Open hole - Arbuckle

1st plug sand back to 3723' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 3 sx hulls, release 8 5/8" rubber plug and pump 175 sx cement.

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 15 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3723' and dumped 5 sx cement on top

of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,

10 sx gel, 3 sx hulls, and 175 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1986

CONSERVATION DIVISION

Maximum pressure 700 psi and shut in 1000 psi

Remarks: Recovered 2022' 5 1/2" casing. Used 60/40 Pozmix by Halliburton. 1-27-86
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE JAN 29 1986

Signed J. A. Metz
(TECHNICIAN)

INV. NO. 12161