

1. 010028

API NUMBER 15- 145-20,955-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 1, T 21 S, R 16 W/E
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5407

Lease Name Barrett Well # 1

Operator: Hupfer Oil & Gas
Name & Address: 3711 Country Lane
Hays, KS 67601

County Pawnee 125.03
Well Total Depth 3847 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 961

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:45 pm Day: 28 Month: August Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3846' Perfs at 3767-69'
1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 pm Day: 28 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement. 9-6-85

RECEIVED STATE CORPORATION COMMISSION

SEP 6 1985

CONSERVATION DIVISION
WICHITA, KANSAS

Maximum pressure 800 psi and shut in 600 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2261' 5 1/2" (If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 10 1985
INV. NO. 9958

Signed [Signature] (TECHNICIAN)