

1052252

5-12

TO: STATE CORPORATION COMMISSION

API NUMBER 15-145-21383-0000
NW NE NE, SEC. 1, T 21 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PHINNEY WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PAWNEE

OPERATOR LICENSE # 3833

WELL TOTAL DEPTH 3895 126.59 FEET

OPERATOR: JOHN H. SHaida PRODUCTION CSG: SIZE 5 1/2" FEET 3894'

NAME AND ADDRESS 4126 N. SWEET BAY CIRCLE SURFACE CASING: SIZE 8 5/8" FEET 1003'

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKES TESTING AND SALVAGE INC LICENSE NUMBER 31529

ADDRESS P. O. BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 11:30 PM DAY: 12 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKES KELSO

(COMPANY NAME) MIKES TESTING AND SALVAGE INC (PHONE) 316-938-2943

WERE: PERFORATIONS 3768-3814

SAND BOTTOM TO 3700' AND PLACE 5 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

SPOT PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 1030' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT.

2ND PLUG AT 500' WITH 40 SX OF CEMENT. 3RD PLUG AT 40' WITH 10 SX OF CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 12 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3700' AND PLACED 5 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 1030' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT

2ND PLUG AT 500' WITH 40 SX OF CEMENT,

3RD PLUG AT 40' WITH 10 SX OF CEMENT

RECEIVED STATE CORPORATION COMMISSION

MAY 18 1998
Richard M. Lopez
5-18-98

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 2228' OF 5 1/2" CASING (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

(I DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lopez (TECHNICIAN) FORM CP-2/3

DATE 5-21-98

INV. NO. 50596