

To: 1 121092.
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

12-13

Operator License # 30108

Operator: Sterling Oil Company, Inc.

Name: _____

Address P.O. Box 306

Sterling, KS 67579

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 13 Month: 12 Year: 19 95

Plugging proposal received from Kent Strube

(company name) DS&W Well Servicing (phone) 316-587-3361

Work: 5 1/2" at 3860' w/175 sx cement, PBD 3809', Perfs at 3797, 3793, 3788'

1st plug sand back to 3740' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement. 12-20-95

RECEIVED

Plugging Proposal Received by _____

KANSAS CORPORATION COMMISSION
Duane Rankin

(TECHNICIAN)

DEC 20 1995

None

Plugging Operations attended by Agent?: All Part _____

Operations Completed: Hour: 1:30 p.m. Day: 13 Month: 12 Year: 1995

CONSERVATION DIVISION

WICHITA, KS

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3740' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10

sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1880' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Conservation to observe this plugging.

INVOICED

JAN 09 1996

DATE

INV. NO.

44466

Signed

Duane Rankin
(TECHNICIAN)