

1 050810

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,244-0000

SE SE SW, SEC. 7, T 21 S, R 15 WEX  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8728

Lease Name Little Well # 1

Operator: Rockhound Resources, Inc.

County Pawnee 126.91

Name & Address P. O. Box 1010

Well Total Depth 3905 Arbuckle feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 950

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Williamson Drilling, Inc. License Number 4087

Address 5501 Navajo, Great Bend, KS 67530

Company to plug at: Hour: 4:00 pm Day: 8 Month: May Year: 19 86

Plugging proposal received from Terry Williamson

(company name) Williamson Drilling (phone) 316-793-8229

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1959' Anhydrite 940'

1st plug in the Arbuckle with 30 sx cement

2nd plug at 980' with 50 sx cement

3rd plug at 400' with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement. Fill up water well.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 7:15 pm Day: 8 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 3875' with 30 sx cement, 2nd plug at 980' with 50 sx cement, 3rd plug at 400' with 40 sx cement, 4th plug from 40' to surface with 10 sx cement,

5th plug to circulate rat hole with 10 sx cement. Filled water well from bottom to top

with cement.

Remarks: Used 60/40 Pozmix 2% gel by Sun Cementing.

(If additional description is necessary, use BACK of this form.)

(did / observe this plugging.

INVOICED

DATE MAY 12 1986

INV. NO. 13770

Signed Richard W. Lacey (TECHNICIAN)

5-8 JUN 26 1986

RECEIVED STATE CORPORATION COMMISSION

MAY 12 1986

CONSERVATION DIVISION Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

15-145-21244-0000

Starting Date April 28, 1986  
month day year

API Number 15-

445-21,244

OPERATOR: License # 8728  
Name Rock Resources, Inc.  
Address P.O. Box 1010  
City/State/Zip Great Bend, KS 67530  
Contact Person James C. Musgrove/Rod Tremblay  
Phone (316) 792-8251

SE SW SW Sec. 7 Twp. 21S, Rg. 15W  
330 Ft. from South Line of Section  
2970 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet  
County Pawnee

CONTRACTOR: License # 4813  
Name Mustang Drilling & Exploration  
City/State Great Bend, KS 316-793-8229

Lease Name Little Well # 1  
Ground surface elevation 1959 feet MSL

Well Drilled For: Well Class: Type Equipment:  
X Oil SWD Infield Mud Rotary  
Gas Inj Pool Ext Air Rotary  
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water  
Depth to bottom of usable water 325

Operator Williamson Drilling, Inc  
Well Name 5501 DAVATO - Great Bend  
Comp Date Old Total Depth 6750

Surface pipe by Alternate: 1 X 2  
Surface pipe planned to be set 8.5/8" @ 950'

Conductor pipe required none  
Projected Total Depth 3900 feet  
Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.

Date 4-23-86 Signature of Operator or Agent James C. Musgrove Title President WW

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 325 feet per Mt. 1 & 4

This Authorization Expires 10-29-86 Approved By 4-29-86

Speed 5-1-86 1:30 pm

950 + 8 5/8 will cost Card for plugging Arduis

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Top Arbuckle feet depth with sxs of 30 SX  
2nd plug @ Base Anhydrite feet depth with sxs of 50 SX  
3rd plug @ Base Surface Pipe feet depth with sxs of 50 SX  
4th plug @ 40' - 0' feet depth with sxs of 10 SX  
5th plug @ feet depth with sxs of  
(2) Rathole with 10 sxs (b) Mousehole with 10 sxs

PUSHER Jerry Williamson

TD 3905 FORMATION Arbuckle

SURFACE PIPE 950 @ 8 5/8"

ANHYDRITE 9.40 ELEVATION 1959

STARTING TIME & DATE 4:00 pm 5/8/86

COMPLETION TIME & DATE 7:15 pm 5/8/86

1st PLUG @ 3875 FT. WI 30 SX

2nd PLUG @ 980 FT. WI 50 SX

3rd PLUG @ 400 FT. WI 40 SX

4th PLUG @ 40 FT. WI 10 SX

RAT HOLE CIRCULATED WI 10 SX

MOUSE HOLE CIRCULATED WI SX

WATER WELL PLUGGED WI filled up SX

CEMENT COMPANY Sun Cementing

TECHNICIAN Lacey sawall

30 SX Arbuckle

50 SX 980

40 SX 400

10 SX 40

10 SX rathole

fill up Water well

RECEIVED STATE CORPORATION COMMISSION  
MAY 12 1986  
CONSERVATION DIVISION  
Wichita, Kansas