

1060329

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,161-0000

SW NE NW, SEC. 7, T 21 S, R 15 W/X
4290 feet from ~~W/S~~ SE Corner of section line
3630 feet from ~~W/S~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8624

Lease Name Button Well # 1

Operator: Genesis Oil & Gas, Inc.

County Pawnee

Name & Address 1505 KSB Building

Well Total Depth 3900 726.75 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 683

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 4:00 pm Day: 11 Month: September Year: 19 84

Plugging proposal received from Craig Christopher

(company name) Allen (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 980' with 80 sx cement

solid bridge

2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement

4th plug to circulate rat hole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:15 pm Day: 11 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 980' with 80 sx cement, 2nd & 3rd plugs - solid

bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to

circulate rat hole with 15 sx cement and plugged water well with 5 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 17 1984

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel by Buie

(if additional description is necessary, use BACK of this form.)

INVOICED (copy) (do not) observe this plugging.

DATE 9-21-84

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 3833

OCT 12 1984