

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-033-21070-00-00  
 Spot: SENENESW Sec/Twnshp/Rge: 17-34S-19W  
2249 feet from S Section Line, 2946 feet from E Section Line  
 Lease Name: HACKNEY B Well #: 1-17  
 County: COMANCHE Total Vertical Depth: 6254 feet

Operator License No.: 34192  
 Op Name: SANDRIDGE EXPLORATION AND PRO  
 Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 70 SX CMT
COND	20	43		
PROD	5.5	5736	1561	WITH 225 SX CMT
SURF	8.625	631		WITH 375 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2017 3:30 PM  
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5000' WITH 20 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL  
 Date/Time Plugging Completed: 05/12/2017 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BRIDGE PLUG AT 5180'. SET CIBP @ 5000'. CIRCULATED 110 BBL MUD THEN SPOTTED 70 SX CMT ON TOP OF BRIDGE PLUG. 1ST PLUG AT 900' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5231	5235		
5210	5227		
5203	5206		
5065	5072		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

INVOICED  
 JUN 14 2017

District: 01

Signed [Signature]  
 (TECHNICIAN)

RECEIVED  
 MAY 18 2017  
 KCC DODGE CITY [Signature]