

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-20506-00-00
Spot: NESWNE Sec/Twnshp/Rge: 15-25S-6W
1650 feet from N Section Line, 1650 feet from E Section Line
Lease Name: ELWARD Well #: 1
County: RENO Total Vertical Depth: 4042 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3647		175 SX
SURF	8.625	255		225 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/19/2017 12:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 04/20/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP AT 3440'. 2 SX CEMENT ON TOP. CASING LEAK AT 850', RUN TUBING TO 850'. COPELAND MIX AND SPOT 35 SX CLASS A 3% CC. AT 10 AM. PULL TUBING. WAIT 2 HOURS AND WIRELINE TAG CEMENT = NOT FOUND. ANOTHER PLUG SET AT 930'. 30 SX CLASS A 3% CC, 200# HULLS. PULL TUBING UP. WAIT 1 HOUR AND WIRELINE TAG AT 1500'. WAIT ANOTHER HOUR AND WIRELINE TAG AT 913'. PERF AT 350' FOR TOP PLUG, PUMP 20 BBL TO SEE IF CIRCULATION WITH TUBING AT 350' = GOOD CIRCULATION. CIRCUALTED TO SURFACE WITH 200 SX 60/40 POZMIX, 4% GEL, 2% CC, 2 SX POLY FLAKES.

Perfs:

Top	Bot	Thru	Comments
3504	3510		

Remarks: COPELAND TICKET #44764, OUT OF GREAT BEND. DENIED TA.

Plugged through: TBG

---INVOICED

JUN 14 2017

District: 02

Signed _____

B. J. Hope

(TECHNICIAN)

1/34