

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21134-00-00  
Spot: NWNESE Sec/Twnshp/Rge: S-32S-19W  
2332 feet from S Section Line, 498 feet from E Section Line  
Lease Name: BIRD RANCH Well #: 1  
County: COMANCHE Total Vertical Depth: 6070 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5144		WITH 2 SX CMT
PROD	5.5	5364	3045	WITH 125 SX CMT
SURF	8.625	720		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2017 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 5144' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2017 11:55 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

\*\*CASING HOLES AT 4316'-4348' WERE SQUEEZED OFF WITH CMT.\*\* SET CIBP @ 5144' WITH 2 SX CMT. 1ST PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 760' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5241	5245		
5214	5220		
5194	5198		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE & CEMENTING.

Plugged through: CSG

INVOICED

JUN 14 2017

District: 01

Signed Eric MacLaren  
SA (TECHNICIAN)

RECEIVED  
MAY 18 2017  
KCC DODGE CITY MP