

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22293-00-01
Spot: E2NWSW Sec/Twnshp/Rge: 4-34S-13W
1980 feet from S Section Line, 4290 feet from E Section Line
Lease Name: FALEN Well #: 2
County: BARBER Total Vertical Depth: 5100 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>33168</u>	PROD	4.5	5100	0	WITH 150 SX CMT
Op Name: <u>WOOLSEY OPERATING COMPANY, LL</u>	SURF	8.625	370		WITH 275 SX CMT
Address: <u>125 N MARKET STE 1000</u> <u>WICHITA, KS 67202</u>					

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/05/2017 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 50 SX CMT WITH 200# HULLS. PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 05/05/2017 4:00 PM

WitnessType: COMPLETE (100%) Not Witnessed
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

****DID NOT PULL CASING. NOT ENOUGH STRETCH**** PUMP 250# HULLS & 50 SX CMT. PERFORATE 4 1/2" CASING AT 850'. PUMPED DOWN CASING WITH 100 SX CMT. DISPLACE CMT TO 800'. PERFORATE 4 1/2" CASING AT 400' & PUMP DOWN CASING WITH 150 SX CMT CIRCULATING CMT TO SURFACE INSIDE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS TO SURFACE WITH CMT.

Top	Bot	Thru	Comments
4900	4993		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

INVOICED

Plugged through: CSG

JUN 14 2017

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAY 10 2017
KCC DODGE CITY