

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-20383-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 30-26S-8E  
1712 feet from S Section Line, 1214 feet from E Section Line  
Lease Name: SACO-DRUMM Well #: 2  
County: BUTLER Total Vertical Depth: 2835 feet

Operator License No.: 35164  
Op Name: JIM SNYDER, INC.  
Address: PO BOX 109  
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2830		80 SX
SURF	8.625	200		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2016 8:00 AM  
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.  
Proposal Rcvd. from: LINDA SNYDER Company: JIM SNYDER Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RUELS & REGS / SAND @ 2665' W/5 SXS, PERF & CIRC. 250'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/30/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2665', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 250'-251'. 12-22-2016, RIH W/1" TUBING ON BACKSIDE OF 5.5" CASING @ 260', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #3116. 12-28-2016, TAGGED CEMENT ON INSIDE 5-1/2" CASING @ 180', TAGGED CEMENT ON BACKSIDE 5-1/2" CASING @ 30'. 12-30-2016, ELITE CEMENTING MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. P&A COMPLETE. 12-30-2016.

Perfs:

Top	Bot	Thru	Comments
2715	2730	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

INVOICED  
JAN 24 2017

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)