

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21965-00-00
Spot: NESWSE Sec/Twnshp/Rge: 30-26S-8E
1045 feet from S Section Line, 1693 feet from E Section Line
Lease Name: DRUMM Well #: 25
County: BUTLER Total Vertical Depth: 2781 feet

Operator License No.: 35164

Op Name: JIM SNYDER, INC.

Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2780		100 SX
SURF	8.625	222		125 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/21/2016 8:00 AM

Plug Co. License No.: 35164

Plug Co. Name: JIM SNYDER, INC.

Proposal Rcvd. from: LINDA SNYDER

Company: JIM SNYDER

Phone: (620) 344-6042

Proposed
Plugging
Method:

AS PER KCC RULES & REGS / SAND @ 2650' W/5 SXS, PERF & CIRC. 270'-0'.

Plugging Proposal Received By: JEFF KLOCK

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/28/2016 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2650', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 270'-271'. 12-22-2016, SWEDGED INTO 5-1/2" CASING, ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL, WELL LOST CIRCULATION. SDON. 12-23-2016, RIH W/1" TUBING ON BACKSIDE OF 5.5" CASING @ 260', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TUBING. RIH W/1" TUBING ON INSIDE 5.5" CASING @ 260', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/25 SXS, TOTAL 125 SXS. CEMENT TICKET #3118. 12-28-2016, TAGGED CEMENT @ SURFACE. P&A COMPLETE 12-28-2016.

Perfs:

Top	Bot	Thru	Comments
2700	2716	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

INVOICED

JAN 24 2017

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)