

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-21523-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 34-26S-19W  
3075 feet from S Section Line, 987 feet from E Section Line  
Lease Name: WHITE A Well #: 1-34  
County: EDWARDS Total Vertical Depth: 4800 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 9342 E CENTRAL  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4730		WITH 2 SX CMT
CIBP		4795		
PROD	4.5	4798	2604	WITH 175 SX CMT
SURF	8.625	362		WITH 275 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/04/2017 10:00 AM  
Plug Co. License No.: 35383 Plug Co. Name: STERLING OILFIELD SERVICES, INC.  
Proposal Rcvd. from: DALE OLLER Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: CIBP @ 4730' WITH 2 SX CMT. PLUG AT 1280' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 80 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/04/2017 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

CIBP @ 4730' & 2 SX CMT. 1ST PLUG AT 1295' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 439' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. HOLE STANDING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4778	4788		MISSISSIPPIAN

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.


Plugged through: CSG

INVOICED

JAN 24 2017

District: 01

Signed



(TECHNICIAN)

SA

RECEIVED  
JAN 11 2017  
KCC DODGE CITY