

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20114-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 30-27S-34W
2752 feet from S Section Line, 2379 feet from E Section Line
Lease Name: COOK E Well #: 2
County: HASKELL Total Vertical Depth: 3150 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3149	825	WITH 275 SX CMT
SURF	8.625	784		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/12/2017 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TBG STUCK AT 2962'. PUMP 25 SX CMT ON TOP OF FISH. WOC & TAG. PLUG AT 1850' WITH 40 SX CMT. PLUG AT 825' WITH 100 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2017 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

COULDN'T GET PASSED 1410' WITH TBG. PUMPED 30 SX CMT AT 1410' WITH GOOD CIRCULATION. CUT & PULL CASING. 1ST PLUG AT 825' WITH 100 SX CMT. 2ND PLUG AT 64' WITH 20 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
2888	2947		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY ORR ENTERPRISES.


INVOICED

Plugged through: TBG

JAN 24 2017

District: 01

Signed


JA

(TECHNICIAN)

RECEIVED
JAN 20 2017
KCC DODGE CITY