

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-01921-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 22-13S-14W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SELLENS D Well #: 2  
County: RUSSELL Total Vertical Depth: 3270 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3270		225 SX
SURF	8.625	208		185 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2017 10:30 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: TODD L. DINKEL Company: MORRIS, TERRY E. DBA G L M CO Phone: (785) 639-5415

Proposed Plugging Method: Ordered 425 sx 60/40 poznix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/11/2017 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

01/10/2017 - Perforated at 208', 870' and 1350'. No show of cement trucks.  
01/11/2017 - Ran tubing to 3030' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2000' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 75 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 55 sx cement. Circulated cement out of the braden head.

GPS: 38.90467 -098.85798

Perfs:

Top	Bot	Thru	Comments
3267	3271		
3025	3040		

KCC WICHITA  
JAN 24 2017  
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2802

Plugged through: TBG

INVOICED  
JAN 24 2017

District: 04

Signed Ray A Dinkel  
(TECHNICIAN)

cm

JAN 17 2016