

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-20745-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 35-7S-26W
1987 feet from S Section Line, 2070 feet from E Section Line
Lease Name: JOHN C SCHEETZ Well #: 1-35
County: SHERIDAN Total Vertical Depth: 3980 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3972		25 SX
SURF	8.625	339		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2017 10:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: RANDALL PFEIFER Company: RL INVESTMENT, LLC DBA Phone: (785) 421-6448

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
8 5/8" surface casing set at 339' w/240 sx cement.
4 1/2" production casing set at 3972' w/150 sx cement.
TD 3980'.
Perforations: 3810' - 3813' and 3761' - 3766'.
Casing leak: 2310' - 2312'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2017 2:10 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2190' and 1450'. Ran tubing to 3771' and pumped 85 sx cement w/200 # hulls. Pulled tubing to 2563' and pumped 85 sx cement w/200 # hulls. Pulled tubing to 1293' and pumped 85 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 5 sx cement. Pressured to 400 psi.

GPS: 39.39839N -100.18779W

Perfs:

Top	Bot	Thru	Comments
3810	3813		
3761	3766		

KCC WICHITA
JAN 24 2017
RECEIVED

Remarks: ALLIED SERVICES LLC TICKET # 68.225

Plugged through: TBG

INVOICED
JAN 24 2017

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM