

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22959-00-01
Spot: NESWNW Sec/Twshp/Rge: 6-7S-20W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WALLER A OWWO Well #: 1
County: ROOKS Total Vertical Depth: 3693 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3749		290 SX
SURF	8.625	311		205 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2016 10:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Tubing stuck at approximately 2000'.
Production perforations: 3420' - 3668'.
Alt II to surface w/300 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2016 1:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to tubing and pumped 150 sx cement. Bottom of anchor at 3690'. Unscrewed at 950' and pumped 75 sx cement. Pulled 950' of tubing and topped off 4 1/2" casing with 10 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pressured immediately.

GPS: 39.47654N -099.59942W

Perfs:

Top	Bot	Thru	Comments
3662	3668		

KCC WICHITA
JAN 24 2017
RECEIVED

INVOICED

Remarks: GLOBAL CEMENTING TICKET # 2805

JAN 24 2017

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM