

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-23789-00-00  
Spot: NENESENE Sec/Twnshp/Rge: 17-25S-16E  
3740 feet from S Section Line, 210 feet from E Section Line  
Lease Name: CUMMINGS B Well #: 25  
County: WOODSON Total Vertical Depth: 991 feet

Operator License No.: 32709

Op Name: SPLECHTER, TIM

Address: 1586 HWY 54  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	1002		110 SX
SURF	7	40		8 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2016 12:00 AM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Rcvd. from: TIM SPLECHTER Company: \_\_\_\_\_ Phone: (620) 496-6100

Proposed Plugging Method: suspect bad casing at 50 ft depth. Plan on running 1 inch hi drill pipe to bottom and washing well then pump cement from bottom to top.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 12/27/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Ran 1" pipe down the inside of the 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 45 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
JAN 17 2017  
CHANUTE, KS  
RD  
KCC WICHITA  
JAN 23 2017  
RECEIVED  
INVOICED  
JAN 24 2017

Remarks:  
Plugged through: TBG

District: 03 Signed Ryan M. Duling, E.C.A.S.  
(TECHNICIAN)