

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23970-00-00  
Spot: S2NWNWSW Sec/Twnshp/Rge: 34-8S-19W  
2145 feet from S Section Line, 330 feet from W Section Line  
Lease Name: AMREIN Well #: 1  
County: ROOKS Total Vertical Depth: 3490 feet

Operator License No.: 32278

String Size Depth (ft) Pulled (ft) Comments

Op Name: TENGASCO, INC.

PROD 5.5 3488 150 SX

Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

SURF 8.625 264 180 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/10/2017 9:00 AM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER WELL SERVICE, INC.

Proposal Rcvd. from: GARY WAGNER

Company: TENGASCO, INC. DBA

Phone: (785) 625-6374

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls and 1500 # gel.  
Port Collar at 1396' w/180 sx cement.  
Production perforations: 3398' - 3406'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/10/2017 11:45 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3350'. Quality Oilwell Cementing pumped 15 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 150 sx cement. Cement circulated. PTOH. Topped off casing w/20 sx cement. Hooked to backside and pumped 10 sx cement. Maximum pressure 500 psi. Shut in pressure 500 psi.

Perfs:

Top	Bot	Thru	Comments
3398	3406		

KCC WICHITA  
JAN 24 2017  
RECEIVED

INVOICED

JAN 24 2017

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JAN 12 2017

Form CP-2/3