

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-02226-00-01
Spot: SESENW Sec/Twshp/Rge: 33-10S-20W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ALLPHIN Well #: 6
County: ROOKS Total Vertical Depth: 3757 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3721		100 SX
SURF	8.625	255		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2016 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS. LLC
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION DBA Phone: (785) 483-9169

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Squeeze jobs: 1002' - 1095' w/105 sx cement and 1265' w/100 sx cement.
Knocked out CIBP at 3550'.
Production perforations: 3204' - 3757'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2016 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3630' and l pumped 75 sx cement w/250 # hulls. Pulled tubing to 2790' and pumped 115 sx cement w/200 # hulls. Pulled tubing to 1520' and pumped 135 sx cement w/200 # hulls to circulated cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 35 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 50 sx cement. Shut in pressure 150 psi.

GPS: 39.14077N -099.55991W

Perfs:

Top	Bot	Thru	Comments
3204	3212		

KCC WICHITA
JAN 24 2017
RECEIVED

INVOICED

JAN 24 2017

Remarks: BASIC CEMENTING TICKET # 13944

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

(M)

DEC 27 2016