

6-9

4-060691

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15-009-03292-0000  
NE NW NE /4 SEC. 12, 16 S, 12 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# 6357 Lease Woydzick well # 2

Operator: Webco Oil Company County Barton

Address: 1303 Baker Well total depth 3301 <sup>107.28</sup> feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 773 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 10:00A.M. Day: 9 Month: June Year: 95

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1995

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [      ], None [      ]

Completed: Hour: 1:00P.M., Day: 9, Month: June, Year: 95

Actual plugging report: 8 5/8" to 773'. 5 1/2" to 3298'. Sanded back to 2850' and spotted 5 sxs. cement with dump bailer. During stretch test to determine cut off point, colar stripped and parted casing at 718'. Attempts to screw back onto casing unsuccessful. Mixed and pumped 130 sxs. cement with 300# hulls. Pulled casing and tied onto surface pipe. Mixed and pumped 60 sxs. cement with 200# hulls. Calculated cement coverage from 718' to 2025' in casing annulus. Pumped cement until well locked up. Max. P.S.I. 800#. S.I.P. 800#. Confirmed damage to bottom colar which had impact damage to prevent screwing back into casing.

Remarks:       
Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation: 1880 GL

I did [ X ] / did not [      ] observe the plugging.

[Signature]  
DH (agent)

**INVOICED**

DATE 6-26-95  
INV. NO. 42999