

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW-NE-SE

SEC. 1 TWP. 21 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Smith

Operator Ben F. Braek Oil Co, Inc. Address #310 Brown Bldg. Wichita-Kans.

Field _____ County Rawnee

Total Depth 3793 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 735 ft. Circulated with cement.
5 1/2 casing set at 3779 ft. - Cemented with 100 sacks cement.
Plugged back to 3770 ft with chat - Pumped 5 sacks of
cement at 3770 ft - Shot off & pulled the 5 1/2 casing
Mud to 750 ft - Pumped in Plug & 200 sacks of
cement - Filling hole from 750 ft - to the surface
with cement.

Cement Pumped in by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1951
CONSERVATION DIVISION
Wichita, Kansas
1-20-51
E. H. Stough
District Conservation Agent

PLUGGING
FILE SEC 1 TWP 21 RGE 16-W
BOOK PAGE 56 LINE 40

Date 1-18-51