

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 123-6

LOCATION NE-SW-NE

SEC. 1 TWP. 21 RGE. 16-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Wm "B"

Operator Mr. Morris Sitem Address Box #160 Tulsa Okla.

Field \_\_\_\_\_ County Nowata

Total Depth 3784 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 985 ft. Cased with cement  
5 1/2 casing set at 3783 ft. 125 sacks of cement -  
dumped 5 sacks of cement on bottom of hole - shot off  
& pulled the 5 1/2 casing - run to 2500 ft - Put Rock Bridge  
& 20 sacks of cement at 2500 ft. run to 3575  
Bridge & 10 sacks of cement at the surface.

The West Supply Co - Plugging Contractors

RECEIVED  
STATE CORPORATION COMMISSION

NOV 26 1951

CONSERVATION DIVISION  
Wichita, Kansas

C. M. Stough  
District Conservation Agent

Date 11-24-51

PLUGGING  
FILE SEC. A.T. 21 R. 16-w  
BOOK PAGE 123 (129) 6

## WISE "B" NO. 2

LOCATION: NE $\frac{1}{4}$  SW $\frac{1}{4}$  NE $\frac{1}{4}$  Sec. 1-21S-16W  
Pawnee County, Kansas

SPUDED: 1-26-50

OPERATOR: Birmingham-Bartlett Drilling Co.

COMPLETED: 2-8-50

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 31 jts., 985' 8-5/8" 28#  
casing cemented @ 983' with 450 sacks  
bulk cement and 4 cc.

OIL STRING: Ran 119 jts., 3786' 5 $\frac{1}{2}$ " casing  
cemented at 3783' with 125 sacks bulk  
cement.

## LOG

(Figures indicate bottom of formation)

0	to	230	Sand and shale	2850	shale
		410	Shale	3095	Shale and lime
		515	Sand	3378	Lime
		590	Shale	3435	Lime and shale
		720	Red bed	3484	Lime
		965	Shale and shells	3525	Broken lime
		975	Shale	3665	Lime
		1005	Anhydrite	3753	Conglomerate
		1435	Shale and shells	3760	Shale
		1790	Shale	3784	Arbuckle
		1850	Lime and shale		
		1920	Lime	3784	Total Depth
		2070	Lime and shale		
		2170	Lime		
		2285	Shale		
		2400	Lime		

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Wise "B" #2 as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me  
this 10th day of February, 1950.

Virian J. Ginger  
Notary Public

My commission expires November 29, 1950.

RECEIVED  
STATE CORPORATE  
NOV 14 1951  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLING  
NE $\frac{1}{4}$  SW $\frac{1}{4}$  NE $\frac{1}{4}$  Sec. 1-21S-16W  
PAWNEE COUNTY, KANSAS