

DISTRICT CONSERVATION AGENT'S REPORT

LR

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 123-5

LOCATION NE-NW-NE

SEC. 1 TWP. 11 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Win "B"

Operator Mr. Morris Sitem Address Box 1160 Tulsa Okla.

Field _____ County Pawnee

Total Depth 3817 Feet.

(Describe briefly the manner in which the well was plugged)

Sucker Pipe 8 3/8 - 10 1/2 ft. Circulated with cement
5/8 casing set at 384 ft. - 150 sacks of cement.
Lower Wells Plug at 3450 ft. Plugged back with chat
to 3420 ft. - Dumped 150 sacks of cement at 3420 ft. Shot of &
hulled the 5/8 casing - mud to 250 ft. Set rock bridges &
20 sacks of cement at 250 ft. - mud to 35 ft. - Bridges &
10 sacks of cement at the sucker.

The West Supply Co. - Plugging Contractor

RECEIVED 11-30-51
NOV 30 1951
C. H. Stough -
District Conservation Agent

PLUGGING
FILE SEC 1 T 11 R 16W
BOOK PAGE 183 LINE 5

Date 11-28-51

*Monsieur Sartre Apurator*WISE (B) WELL #1

Location: Approx. Center NE/4 NW/4 NE/4 Sec. 1-21S-16W
Pawnee County, Kansas

Operator: W. N. Bartlett Spudded: 6-15-47

Contractor: H H & B Drilling Co., Inc. Oil String Cemented: 6-30-47

Casing Record: Surface Casing: 33 Jts. Total Depth: 3817'

8-5/8" 8 rd. thd. 28# casing
@ 1023'. Cemented with 350
sacks cement and 3 CC. Oil
string: 123 Jts. 5-1/2" OD 14#
H-40 8 rd. thd. @ 3814'. Cemented
with 150 sacks cement

LOG

(Figuers indicate bottom of formation)

| | | | | |
|--------------------|------|------|----------------------------|------|
| Surface soil | 0 to | 10 | Elevation: (Kelly Bushing) | 1996 |
| Sand and redbed | | 80 | | |
| Shale and shells | | 400 | | |
| Sand | | 540 | <u>Formation Tops</u> | |
| Shale and redbed | | 1010 | Anhydrite | 1005 |
| Anhydrite | | 1036 | | |
| Shale and shells | | 1360 | Brown Lime | 3408 |
| Redbed and salt | | 1775 | Lansing | 3418 |
| Shale and lime | | 2150 | | |
| Lime | | 2325 | Base Kansas City | 3656 |
| Lime and shale | | 2880 | | |
| Shale and shells | | 2945 | Conglomerate | 3696 |
| Lime and shale | | 3115 | | |
| Lime | | 3305 | Simpson | 3730 |
| Lime and shale | | 3415 | | |
| Lime | | 3460 | Arbuckle | 3767 |
| Broken lime - soft | | 3539 | | |
| Lime | | 3669 | | |
| Shale and lime | | 3695 | | |
| Lime | | 3769 | | |
| Arbuckle lime | | 3817 | T. D. | |

PLUGGING
FILE SEC. 1-21S-16W
BOOK PAGE 122 LINE 5

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1951
CONSERVATION DIVISION
Wichita, Kansas