

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas



FILE NO. \_\_\_\_\_

LOCATION SE. 510 - SE

SEC. 1 TWP. 21 RGE. 16W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Smith

Operator Beach Oil Co Address #309 - Beacon Bldg. Wichita - Kans.

Field \_\_\_\_\_ County Rever

Total Depth 3780 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 940 ft. Circulated with cement.  
5 1/2 casing set at 3745 ft. Plugged back from  
bottom to 3740 ft with shot - dumped 5 sacks of cement  
in the 5 1/2 casing at 3740 ft - Shot off & pulled the 5 1/2 casing  
Filled with mud to 250 ft - Set Rock Bridge &  
15 sacks of cement at 250 ft - Mud to 30 ft - Bridge  
& 10 sacks of cement at the surface

**PLUGGING**  
FILE SEC 1 TWP 21 R 16W  
BOOK PAGE 182 LINE 45

REC'D District Conservation Agent  
C. W. Stough

Date Nov. 1 - 49

NOV 5 1949

STATE CORPORATION COMMISSION  
KANSAS  
11-5-49

