

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty  
 Complete Address: 800 Bitting Bldg Wichita, Kans  
 Lease Name Barret Well No. 2  
 Location SW SW SW Sec. 1 Twp. 21 Rge. (E) (W) 16  
 County Pawnee Total Depth 3808  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated: \_\_\_\_\_  
 Plugging Contractor: Glenn & Smith  
 Address: Ellinwood, Kans License No. 396  
 Operation Completed: Hour 3PM Day 25 Month 10 Year 24x 64

The Above well was plugged as follows:

8 5/8" 979' circulated with cement - 5 1/2" 3800' with 100 sax cement.

Sand to 3990', set 5 sax cement with dump bailer - pulled 3225' 5 1/2"

to 700', circulated hole with heavy mud through 5 1/2" at 700' ( 28 sax Gel)  
 displaced 20 sax cement through 5 1/2" at 700', heavy mud to 240', displaced  
 20 sax cement through 5 1/2" at 240', heavy mud to 35', cement 35' to Bottom  
 of cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 10/29/64

INV. NO. 74-11

Signed: Edna Perry  
Well Plugging Supervisor