

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SE-NW

SEC. 1 TWP. 21 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Spreier

Operator Ben F. Brock Oil Co. Address #310 Brown Bldg. Wichita-Kans.

Field _____ County Rawl

Total Depth 3787 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/4 - 584 ft. Circulated with cement
4 1/2 casing set at 3787 - cemented with 125 sacks cement.
Plugged back to 3770 ft. with chat - Pumped
5 sacks of cement at 3770 ft. - Shot off & pulled the
4 1/2 casing - mud to 600 ft. - Pumped in Plug &
175 sacks of cement. Filling hole from 575 ft
& the surface with cement.*

Pumped in by - Halliburton

RECEIVED
STATE CORPORATION COMMISSION

JAN X 2 1951 1-2-51

CONSERVATION DIVISION
Wichita, Kansas

C. W. Strong
District Conservation Agent

Date 12-28-50

5

PLUGGING
FILE SEC 1 TWP 21 R 16
BOOK PAGE 5 LINE 41