

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tec Exploration Co
Complete Address: c/o Petroleum Management 1515 Wichita Plaza, Wichita,
Lease Name Rosebush Well No. 1
Location SE SW NW Sec. 5 Twp. 21 Rge. (E) (W) 15
County Pawnee Total Depth 3865
Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated: _____
Plugging Contractor: Ace Pipe Pulling & Halliburton Co
Address: Great Bend, Kans License No. 2
Operation Completed: Hour 3PM Day 8xx ¹¹ Month ⁴ Year 64

The Above well, was plugged as follows:

8 5/8" 971' circulated with cement - 5 1/2" 3865' with 100 sax cement -
PB 3815' Perforated 3778' - sand back to 3760', set 4 sax cement.

Pulled 1995' 5 1/2" - well flowing water - pumped 40 sax gel mud - pumped
wiper plug followed by 100 sax cement - squeezed with 100 sax cement 2%
chloride at 750# pump pressure.

Mudding and cementing by Halliburton Co - 600# pump pressure on mud
750# " " on cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/15/64
INV. NO. 8946-W