

SP

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

FEB 11 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Fender Pipe & Supply Co  
Complete Address: Box 302 Russell, Kans  
Lease Name Sprier Well No. 1  
Location SW NW SW Sec. 5 Twp. 21 Rge. (E) (W) 15  
County Pawnee Total Depth 3850  
Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Knight Casing Pulling Co  
Address: Chase, Kansas License No. 436  
Operation Completed: Hour 5PM Day 3 Month 2 Year 65

The Above well was plugged as follows:

8 5/8" 955' circulated with cement - 5 1/2" 3859' with 125 sax cement.  
Perf 3774'

Sand back to 3774' set 5 sax cement with dump bailer - pulled  
3060' 5 1/2" to 940' - circulated hole with heavy mud through 5 1/2"  
( 22 sax Gel) displaced 25 sax cement through 5 1/2" at 325' - heavy mud  
to 135' displaced 25 sax cement through 5 1/2" at 135', heavy mud to 55'  
set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Edon Petty  
Well Plugging Supervisor

DATE 2-11-65  
INV. NO. 674-W