

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1964

3-25-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Davis Mud & Chemical
Complete Address: Box 523 Great Bend, Kans
Lease Name Sweeney Well No. 1
Location NW NW NE Sec. 8 Twp. 21 Rge. (E) (W) 15
County Pawnee Total Depth 3818
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Pipe Pullers Inc
Address: Ellinwood, Kans License No. 462
Operation Completed: Hour 12 Noon Day 21 Month 3 Year 64

The Above well was plugged as follows:

8 5/8" 937' circulated with cement - 5 1/2" 3818' with 75 sax cement

Perforated 3736'

Sand back to 3700', set 4 sax cement with dump bailer - pulled 3008'
5 1/2" to 900' circulated hole with heavy mud through 5 1/2" at 900' (23 sax Gel
pulled 5 1/2" to 340', displaced 25 sax cement through 5 1/2" at 340', heavy
mud to 200', displaced 25 sax cement through 5 1/2" at 200', heavy mud to
35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Pipe Pullers pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/26/64
INV. NO. 8855-u