

46
KANSAS
STATE CORPORATION COMMISSION

15-009-15743-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1963

CONSERVATION DIV.
WICHITA, KANSAS

Operator's Full Name Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name Nick Well No. # 3

Location NE SW SW Sec. 12 Twp. 16 Rge. 12W (E) (W)

County Barton Total Depth 3326

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch's Casing Pulling

Address: Route 4, Great Bend, Kansas License No.

Operation Completed: Hour 4 PM Day 10 Month 4 Year 1963

The Above well was plugged as follows:

No surface pipe.

Set bottom plug @ 2900' & 5 sac cement with dump bailer. Pulled pipe.

Run tubing to 315'; circulated hole with mud. Pulled a joint of tubing

& displaced 50 sac cement thru tubing @290' with pump truck. Pulled

remaining tubing; set rock bridge @ 25', & run 25 sac cement, cementing

to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/15/63

INV. NO. 6892-W

Signed: *Lawrence J. Thomas*
Well Plugging Supervisor