

*110*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-009-15742-0000

RECEIVED  
STATE CORPORATION COMMISSION

JUL 22 1965  
07-22-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name Nick Well No. # 2

Location C NL SE SW Sec. 12 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3332

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ralph Lynch's Casing Pulling Company

Address: RT. # 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 4:30 PM Day 19 Month 7 Year 1965

The Above well was plugged as follows:

No surface pipe. Old Cable tool hole.

Set bottom plug @ 2700' & displaced 5 sax cement with dump bailer.

Pulled pipe. Run 2" tubing to 340'; circulated hole with mud; displaced

40 sax cement thru tubing with pump truck @ 300'. Pulled tubing. Set

rock bridge @ 30' & displaced 40 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Dave Truman  
Well Plugging Supervisor

DATE 7/22/65

INV. NO. 1504-W