

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply Co
 Complete Address: Box 562 Great Bend, Kansas
 Lease Name Spreier Well No. X 2
 Location SE SE NE Sec. 7 Twp. 21 Rge. (E) (W) 15
 County Pawnee Total Depth 3822
 Abandoned Oil Well Gas Well x Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Pipe Pullers Inc
 Address: Ellinwood, Kans License No. 462
 Operation Completed: Hour 2PM Day 9 Month 2 Year 63

The Above well was plugged as follows:

8 5/8" 949' circulated with cement - 5 1/2" 3822' with 150 sax cement.
Perforated 3782'

Filled with sand 3740' set 4 sax cement with dump bailer, pulled 1887' - 5 1/2"
to 520' circulated hole with heavy mud through 5 1/2" at 520', displaced 25 sax
cement through 5 1/2" at 350', heavy mud to 175', displaced 25 sax cement
through 5 1/2" at 175', heavy mud to 35', set bridge and filled to bottom
cellar with cement.

Mudding and cementing by Pipe Pullers Inc Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Letley
Well Plugging Supervisor

DATE 2/12/63
INV. NO. 6593-W