

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-145-21,244-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Rockhound Resources, Inc. OPERATORS LICENSE NO. 8728

ADDRESS P.O. Box 1010, Great Bend, Ks. 67530 PHONE # (316) 792-8251

LEASE (FARM) Little WELL NO. 1 WELL LOCATION SE SE SW COUNTY Pawnee

SEC. 7 TWP. 21S RGE. 15W (E) or (W) TOTAL DEPTH 3905 PLUG BACK TD 3875'

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 950' CEMENTED WITH 400 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Bottom Plug @ 3875' w/30 sks. Cement thru Drill Pipe; Next Plug @ 980' w/50 sks. Cement thru Drill Pipe; Next Plug @ 400' w/40 sks. Cement thru Drill Pipe; Top Plug @ 40' w/10 sks. Cement thru Drill Pipe; 10 sks. Cement in Rathole; 10 sks. Cement in Water Well. Well Plugged w/150 sks. 60/40 Poz, 4% Gel, 3% CC.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? To be Filed by Operator
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5-8-86 4:00 P.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Terry L. Williamson PHONE # (316) 793-8229

ADDRESS 5501 Navajo, Great Bend, Ks. 67530

PLUGGING CONTRACTOR Williamson Drilling, Inc. LICENSE NO. 4087

ADDRESS 5501 Navajo, Great Bend, Ks. 67530 PHONE # (316) 793-8229

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Terry L. Williamson
(Operator or Agent)

7-31-86

DATE: May 14, 1986

JUN 3 1986