

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

15-009-01363-0001

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER N/A 11-4-44 (of this well). 4/90  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Range Oil Company, Inc. OPERATOR'S LICENSE NO. 5120

ADDRESS 1120 KSB&T Bldg. 125 N. Market, Wichita, Kansas PHONE # (316) 265-6231

LEASE (FARM) Woydziak WELL NO. 1 WELL LOCATION S/2 SW NE COUNTY Barton

SEC. 12 TWP. 16 RGE. 12W (E) or (W) TOTAL DEPTH 3338 PLUG BACK TD -

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 10-3/4 SET AT 244 CEMENTED WITH ? SACKS \_\_\_\_\_

CASING SIZE 5-1/2 SET AT 3330 CEMENTED WITH ? SACKS \_\_\_\_\_

PERFORATED AT 2878-2884; 3073-3077; 3125-3128; 3172-3182; 3205-3210; 3222-3230  
Squeezed w/100 sx @ 2878' on 6-5-72

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Shoot off and remove casing @ 1900'. Plug as  
recommended by State of Kansas.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? N/A  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: \_\_\_\_\_

Gilbert Finley PHONE # (316) 1021-6345

ADDRESS R.R. #3 Box 42, Winfield, Kansas 67156

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. 6050

ADDRESS Box 347, Chase, Kansas 67524 PHONE # (316) 938-2943

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: John M. Walker  
(Operator or Agent)

DATE: July 13, 1989

4


RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
6/90

Company - BLACK-MARSHALL OIL CO.  
 Farm - Woydziak No. 1.

SEC. 12 T. 16 R. 18 W  
 C 5 1/2 ST NE

Total Depth. 3338'  
 Comm. 9-9-44 Comp. 11-4-44?  
 Shot or Treated. 11-7-44 1000 Gals. Acid  
 Contractor. Harnum Drlg. Co.  
 Issued. 12-9-44

County. Barton.  
 KANSAS



Elevation. 1892

CASINGS:  
 10 3/4" 244' Cem.  
 5 1/2" 3325' Gr. Meas., Cem.

Production. Phy. Pot. 310 BC  
 plus 2% wtr

Figures Indicate Bottom of Formations.

shale	220
shale & sand	235
shale & lime shells	276
shale	390
sand & shale	480
shale & shells	540
shale	735
lime	751
shale	773
anhydrite	791
shale & shells	1150
shale & salt	1313
salt	1510
shale & shells	1755
lime brkn	1853
lime	1916
lime brkn	1976
lime	2046
lime brkn	2350
shale & shells	2400
lime brkn	2453
shale & shells	2490
lime	2544
lime brkn	2730
lime	3046
KC lime	3110
lime	3319
congl	3329
Arbuckle lime	3332
Total Depth (Rot. Meas)	
lime	3338
Total Depth.	

Top: Lansing 3045 DFM  
 Arbuckle 3327

RECEIVED  
 STATE GEOLOGICAL COMMISSION  
 JUL 14 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH MCCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE  
OCT 21 1989  
EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

July 21, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

Range Oil Company, Inc.  
1120 KSB&T Bldg.  
125 N. Market  
Wichita, KS 67202

Woydziak #1  
S/2 SW NE  
Sec. 12-16S-12W  
Barton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #4 2301 E. 13th  
Hays, KS 67201  
(913) 628-1200